Fixed Ladder Systems: Improvement Proposal based on OSHA Compliance Findings

Author: Ricardo A. Ruiz Velez
Advisor: Dr. Rafael A. Nieves-Castro, PharmD.
Master in Manufacturing Competitiveness
Graduate Project EXPO, February 2026

Abstract

Fixed ladders are critical access systems in industrial facilities, yet deficiencies in their design pose significant safety and regulatory risks. This design project evaluated 19 external fixed ladders at a biotechnology facility for compliance with applicable OSHA requirements. Field inspections, dimensional measurements, and photographic documentation were compared against OSHA fixed ladder and fall protection standards. Widespread partial compliance was identified, with recurring deficiencies related to ladder clearances, surface conditions, corrosion, and fall protection. Project deliverables include the proposal of a conservative internal fall-protection benchmark of 16 ft and a contractor-ready scope of work for modification implementation.

Introduction

Fixed ladders provide routine access to rooftops, platforms, and utility areas in industrial facilities and are integral to safe site operations. These systems are subject to OSHA requirements and pose significant fall risks if improperly designed or maintained. This project addresses the need for systematic fixed ladder compliance assessments as part of continuous improvement in industrial safety management.

Background

Falls remain one of the leading causes of occupational injuries and fatalities in industrial and construction environments. OSHA regulations establish specific requirements for fixed ladder geometry, clearances, surface conditions, and fall protection systems. Recent regulatory changes have phased out ladder cages as acceptable fall protection, shifting emphasis toward engineered systems such as personal fall arrest systems (PFAS). These evolving requirements highlight the importance of reassessing existing ladder infrastructure.

Problem

An internal EHS audit identified potential compliance gaps in several external fixed ladders at a biotechnology facility, particularly related to outdated ladder cages and fall protection provisions. While initial findings focused on travel restraint and cage systems, a broader engineering evaluation revealed additional dimensional, structural, and access-related deficiencies. The absence of a consolidated, ladder-specific compliance assessment created uncertainty regarding regulatory exposure and worker safety, motivating this design project.

Methodology

Nineteen external fixed ladders were evaluated through on-site inspections using tape measurements, visual assessments, photographic documentation, and OSHA-based checklists. Each ladder was assessed individually against dimensional, clearance, surface condition, structural integrity, and fall protection requirements derived from OSHA 29 CFR 1910.23, 1910.28, 1910.29, and 1926.1053. Ladder locations were mapped on site blueprints to support spatial traceability.

Compliance classifications were defined as follows: compliant ladders met all evaluated OSHA criteria; partially compliant ladders met a majority of requirements (at least 8 of 15 evaluated criteria) but exhibited minor deficiencies or improvement opportunities; and non-compliant ladders exhibited major deficiencies, including but not limited to excessive pitch, absence of required fall protection, significant corrosion, or dimensional non-conformities that could not be corrected through minor modification. A conservative internal fall-protection benchmark of 16 ft was adopted. Contractor walkthroughs were conducted to validate feasibility and develop a contractor-ready scope of work.

Table 2: Aggregated Deficiency Counts

Compliance criterion	Non-Compliant Ladders per OSHA	Could be improved
Spacing Between Rungs	0	0
Width of Rungs	1	0
Perpendicular Clearance Behind Ladder	5	0
Width to nearest permanent object (sides)	5	0
Step-across Distance to access point	12	0
Side Rail Extensions over access level	3	0
Side Rail Flaring	3	0
Grab Bars present, extend 42" above access level and must not protrude	8	2
Perpendicular Clearance on the Climbing Side	2	0
Non-Slippery Rung Surface or Textured Rungs	16	3
PFAS when required	1	2
Pitch	1	0
Steps Omitted from access point	0	0
Hatch Ladder Clearances	0	0
Openings over 4' (Travel Restraint System)	7	0



Image courtesy of Charles Brown of the University of Florida [8].

Highlighted in red are the dimensions under evaluation by the project engineering department.

Results and Discussion

Only one of the nineteen evaluated ladders was fully compliant with all assessed OSHA criteria. Eleven ladders were classified as partially compliant, while seven were non-compliant due to major safety deficiencies. The most common issues included inadequate rung slip resistance, insufficient clearances, non-compliant step-across distances, corrosion, and outdated ladder cage systems.

Several ladders exhibited notable non-compliance requiring significant intervention. Ladder #24 (East Yard) failed both pitch and rung width requirements, necessitating full replacement. Ladders #40, #45, #46, #47, and #48, located in high-traffic roof access areas, showed advanced corrosion and structural degradation, rendering modification impractical and justifying replacement. Underground waste pit ladders (#28, #29, and #30) presented compounded hazards due to confined space geometry and clearance constraints, requiring engineered clearance corrections and improved access guidance.

Adoption of an internal 16-ft fall-protection benchmark resulted in additional personal fall arrest system recommendations beyond OSHA minimums, reinforcing a proactive approach to fall risk mitigation.



Ladder Evaluation Summary

Ladder	Evaluation Criteria												
	A	SLIPPERY	B	C	D	PFAS & HEIGHT	PITCH	E	F	STEPS OMITTED	G	H	I	HATCH LADDER	OPENINGS
#44 — Guard House						13'			N/A		N/A			N/A	
#1 — Roof Building A						13.6'									N/A
#41 — Behind 1st Floor Labs A						20.3'								N/A	
#42 — Behind 1st Floor Labs B						9.9'								N/A	
#43 — Behind Area 7						24.3'								N/A	
#39 — Behind Cafeteria						22'								N/A	
#46 — Building A and Building B Link – Roof A						6.6'								N/A	
#47 — Building A and Building B Link – Roof B						8.5'								N/A	
#48 — Building A and Building B Link – Roof A						4.1'								N/A	
#28 — Waste Pit (West)						11.3'								N/A	
#29 — Waste Pit (South)						12.5'								N/A	
#30 — Waste Pit (North)						19.2'								N/A	
#33 — Tank Ladder						11.0'								N/A	
#40 — Building A and Building B Link – Main Roof						13.6'								N/A	
#24 — East Yard Ladder						24.0'								N/A	
#45 — Recycling Roof						4.1'								N/A	
#49 — Pipe Rack Ladder						16.0'								N/A	
#32 — Salt Pit Exterior						8.9'								N/A	
#10 — Roof Building B						12.6'			N/A		N/A			N/A	

Comply | Do not Comply | Comply but could be improved

A	Spacing Between Rungs	F	Side Rail Extensions over access level
B	Width of Rungs	G	Side Rail Flaring
C	Perpendicular Clearance Behind Ladder	H	Grab Bars 42" above access level
D	Width to nearest permanent object (sides)	I	Perpendicular Clearance on the Climbing Side
E	Step-across Distance to access point		

REPLACE FOR A NEW ONE.
Please provide prices for different build materials.
Scaffold Required.

FL-24

Criteria	Requirement	As found	Comments
Rungs, cleats and steps spacing (Drawing A)	"X" ≥ 10"; "X" ≤ 14"	13"	
Clear distance between the side rails (Drawing B)	"X" ≥ 16"	15.5"	Ladder will be made NEW for lacking compliance with this criteria.
Rungs and steps (Slipping)	Corrugated		Paint for Corrosion Protection & Fine Sand Treatment (Anti-Slip)
	knurled		
	dimpled		
	coated with skid-resistant material		
	treated to minimize slipping		
Perpendicular clearance			
- between rungs, cleats and steps, and any obstruction behind the ladder (Drawing C)	"X" ≥ 7"	50"	
- between the centerline of rungs, cleats and steps and any obstruction on the climbing side of the ladder (Drawing C)	≥ 30" ["X" could be < but ≥ 24" provided that a deflection device is installed to guide employees around the obstruction	27"	REMOVE CAGE. Scaffold required.
Width to the nearest permanent object (Drawing D)	"X" ≥ 15"	14.5"	REMOVE CAGE. Scaffold required.
Ladder length of climb > 24'	Fall Arrest System?	YES	Ladder Height: 24.1'
	Ladder Safety System?		
Pitch	"X" = 90° from the horizontal, as measured to the back side of the ladder.	!	New ladder will have a corrected pitch of 90 degrees.
Through fixed ladders			
- Point of access/egress step-across distance: (Drawing E)	"X" > 7" but ≤ 12". If "X" > 12", a landing platform is required.	9"	
- Side rails extensions (Drawing F)	"X" ≥ 42" above the top of the access level or landing platform served by the ladder.	44"	
- Steps or Rungs	Omitted from the extensions		
- Side Rails (Drawing G)	Flared to provide "X" ≥ 24" but "X" ≤ 36"	24"	
- Grab bars (Drawing H)	42" above the access level or landing platform served by the ladder		
Hatch ladder	Opens with sufficient clearance to provide easy access to or from the ladder	(N/A)	
	Opens at least 70° from horizontal if the hatch is counterbalanced	(N/A)	
Openings	Opening is 4 feet (1.2 m) or more above a lower level?		
	"Guardrail system"		
	"Safety net system"		
	"Travel restraint system"		Replace Swing Gate
	"Personal fall arrest system"		

Conclusions

- A structured OSHA-based assessment revealed widespread partial compliance and systemic ladder deficiencies.
- Most deficiencies were related to geometry, surface conditions, and fall protection rather than isolated damage.
- The removal of ladder cages and adoption of a conservative fall-protection benchmark improved hazard identification.
- The project successfully translated regulatory findings into actionable engineering controls and implementation plans.

Future Work

- Expand evaluations to include ANSI and NIOSH guidance for enhanced ladder safety criteria.
- Develop quantitative risk prioritization models incorporating ladder usage frequency and environmental exposure.
- Conduct longitudinal studies to assess post-modification incident and near-miss trends.
- Apply the methodology to other fixed access systems across the facility.

Acknowledgements

The author acknowledges the support of the Environmental Health and Safety Department and the Project Engineering team for their collaboration during inspections and evaluations. Appreciation is also extended to external contractors for their technical input during walkthroughs and feasibility assessments.

References

1. Cheng et al., Automation in Construction, 2024
2. OSHA, 29 CFR §1910.23
3. OSHA, 29 CFR §1910.28
4. Ajslev et al., Int. J. Environ. Res. Public Health, 2022
5. OSHA, 29 CFR §1910.29
6. OSHA, 29 CFR §1926.1053
7. Jin & Goodrum, Applied Sciences, 2021
8. Gorucu et al., EDIS AE570, 2022
9. Welborn & Boraiko, Professional Safety, 2009